

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-20264-0000

SW SW NW, Sec. 36, T 7 S, R 18 (W) ~~18~~
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114

Lease Name Flint Well # 1

Operator: J. Mark Richardson Co.
Name & 640 Centry Plaza
Address Wichita, Ks.

County Rooks

Well Total Depth 3325 feet 108.07

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Company License Number _____

Address Box 31, Russell, Kansas 67665

Company to plug at: Hour: 2 PM Day: 13 Month: April Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Carl Shields

(company name) Mark Richardson Company (phone) (316) 262-3192

were: 8 5/8" 215' S.P. CUC w/150 sks 4 1/2" CSG set @ 3324' w/100 sks cmt D.V. Tool Set @ 1261 (Anhydrite) w/450 sks cmt. CUC, no pipe recovery.

Ordered 160 sks 50/50 pozmix 6% gel 3% cal. cl., 8 sks gel, 4 sks hulls, 4 1/2" plug. Pump in with pump truck, annulus and 4 1/2" CSG. Elev. 1864 Anhy 1233.

Signed *Marion Schmidt*
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 PM Day: 13 Month: April Year: 1984

ACTUAL PLUGGING REPORT Ordered 160 sks 50/50 pozmix 6% gel 3% cal. cl. - 8 sks gel, 4 sks hull's and 4 1/2" plug. Pumped in annulus between 4 1/2" CSG and 8 5/8" S.P. pressured to 1000 PSI Annulus wouldn't take cement, pumped in 4 1/2" CSG 35 sks cmt. w/3 sks hull's mixed in, 8 sks gel, released plug and 100 sks cmt. max PSI 200 Lbs. Cemented by Allied Cementing Company

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1984
CONSERVATION DIVISION
Wichita, Kansas
4-23-84

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed *Marion Schmidt*
DOIC (TECHNICIAN)

INVOICED

DATE 4-24-84

INV. NO. 1234 APR 27 1984