

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21703-00^{X02}
Spot: CNWSWNE Sec/Tynshp/Rge: 25-7S-18W
3630 feet from S Section Line, ¹⁹⁸⁰4950 feet from E Section Line
Lease/Unit Name: KU ENDOWMENT Well Number: 1
County: ROOKS Total Vertical Depth: 3310 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size 13.375 feet: 140 ^{3107.58}
Surface Casing: Size 8.625 feet: 1185 425 SX CMT
Production: Size 5.5 feet: 3307 135 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/04/2002 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 727-3409

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perfs 3216'-3255'; 3169'-3173'; 2969'-2972'.
CIBP 3278'.

Plugging Proposal Received By: CASE MORRIS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/04/2002 4:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 2806' w/5 sxs cement.
Shot 5 1/2" casing off at 2255'. Pulled to 1700'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled to 1250'. Allied pumped 40 sxs at 1250' w/100# hulls.
Pulled casing to 650'. Allied pumped 30 sxs cement.
Pulled to 200' - circulated cement with 55 sxs cement.

RECEIVED
DEC 11 2002
KCC WICHITA
12-11-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-12-02

INVOICE NO. 2003060930

DEC 10 2002

RIM OIL COMPANY
512 S. WYOMING

REPLACEMENT CARD

#1 K.U. ENDOWMENT ASSN., INC.


25-7-18W
NW SW NE

PLAINVILLE, KS 67663
CONTR PIONEER DRILLING CO.

CTY ROOKS

GEOLOGICAL

FIELD RIFFE



ELV 1757 KB SPD 6/18/82 CARD ISSUED 9/9/82 IP P 15 BO & 85 BWPD
1752 GL ARB 3232-3265

API 15-163-21,703

SMP	Tops	Depth/Datum
SC	1172+	585
B SC	1212+	545
TOP	2678-	921
TOR	2910-	1153
KC	2930-	1173
BKC	3157-	1400
MARM SD	3162-	1405
MARM LM	3191-	1434
ARB	3221-	1464
RTD	3310-	1553

13 3/8 " COND AT 140/140SX; 8 5/8 " 1185/425SX; 5 1/2 " 3307/135SX
NO DST'S
MCT - CO, PF (ARB) 3232-65 W/2 SPF, AC 500G (MA) & 2250G (15% REG), SWB DWN, GSO, POP, P 15 BO & 85 BWPD (GR 24°), 7/28/82

CORRECTION: 4/14/83 - PROD INTV WAS OH 3307-10

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS