

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,818-00-00

NE, Sec. 29, T 7 S, R 18 WE

1980 feet from N/S section line

660 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5073

Lease Name Civin lower Well # 1

Operator: Eagle Exploration
Name &
Address 300-107 N. Market
Wichita, Mo. 67202

County Rocks

Well Total Depth 3445 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1264

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor McDonald Drilling Co. License Number _____

Address 300-107 N. Market, Wichita, Mo. 67202

Company to plug at: Hour: 9:00 PM Day: 15 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Jack Fox

(company name) McDonald Drilling Co. (phone) 316-265-2892

were: Order out 190 sacks 50 permix - 4% gel - 3% lat. cl. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs 1st plug C 3445' w/ 15 sacks, 2nd plug C 1244' w/ 15 sacks, 3rd plug C 720' w/ 70 sacks, 4th plug C 300' w/ 40 sacks, 5th plug - solid bridge of bulls + plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Signed Edith R. Hibel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 PM Day: 15 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 1264' SP. CUC. W/ 500 sacks common - 2% gel - 3% lat. cl. Ordered 190 sacks 50 permix - 4% gel - 3% lat. cl. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs 1st plug C 3445' w/ 15 sacks, 2nd plug C 1244' w/ 15 sacks, 3rd plug C 720' w/ 70 sacks, 4th plug C 300' w/ 40 sacks, 5th plug - solid bridge of bulls + plug C 40' w/ 10 sacks. Circulated 10 sacks in rat hole + 10 sacks in mouse hole.

Remarks: _____

STATE CORPORATION COMMISSION
RECEIVED
NOV 1 1982
CONSERVATION DIVISION
Wichita, Kansas
11-1-82

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Edith R. Hibel
(TECHNICIAN)

INVOICED

DATE 11-15-82

INV. NO. 1560 W

FORM CP-2/3
Rev. 9-82