

4-041805

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-2

API Number: 15-163-22,873 -00-00
10'S. & 30'E. of
NW NE SE /4 SEC. 25, 07 S, 18 W
2300 feet from S section line
960 feet from E section line

Operator license# 8925

Lease: Jayhawk Well # 1

Operator: Liberty Operations & Completions Inc.

County: Rooks 110.30

Address: 308 W. Mill
Plainville, Kansas 67663

Well total depth 3394 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 274 feet
w/160 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00 A.M. Day 2 Month: October Year 1996

Plugging proposal received from: Roger Comeau

Company: Liberty Operations & Completions, Inc. Phone: 913-434-4686

Were: 5 1/2" casing set at 3394' w/150 sxs cement. Perf. at 3332' - 3381'.
Anhy. at 1300' cemented with 375 sxs.
Ordered 150 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 200# hulls - 18 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 1:00 P.M., Day 2, Month: October, Year: 1996

Actual plugging report: R.U. Cementers to 5 1/2" casing. Squeezed 35 sxs cement with 200# hulls, followed with 18 sxs gel, followed with 100 sxs cement with 100# hulls. Max. P.S.I. 1500#. 8 5/8" S.P. Pressured-up to 1500#.

Remarks: Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel (agent)
Form CP-2/3

RECEIVED
OCT 17 1996
10-9-96

INVOICED
DATE OCT 17 1996
BILL NO. 46710
10-2