

6 070374

PLUGGED

API NUMBER 15-162-22, 702-00-00

For:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE-SE-NW, SEC. 25, T. 7 S, R. 18 W

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9476

Lease Name HAZEN Well # 1

Operator: G.D. OIL OPERATIONS

County ROOKS 107.55

Name & Address P.O. BOX 441

Well Total Depth 3309 feet

HAYS, KANSAS 67601

Conductor Pipe: Size 0 feet

GLEN DROTTS

Surface Casing: Size 8 5/8 feet 3309

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒

Other well as hereinafter indicated 216 #49 #617

Plugging Contractor R. T. C. DRILLING CO., INC. License Number 9087

Address HAYS, KANSAS, 67601

Company to plug at: Hour: 6:00 AM Day: 23 RD Month: JULY Year: 1985

Plugging proposal received from JOHN WEIS

(company name) R. T. C. DRILLING CO. (phone) 913-628-2560

were: 8 5/8" 1199 FT SP. CMC 1/450 SK COMMON GEL-CA-CL, (BY ALLIED CMT.)

ORDER 210 SK 60/40 POZ MIX GEL-CA-CL - AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, RECONDITION HOLE (VISCOUSITY) HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, MUD CONDITION 45 VISCOSITY, HOBKYLE 3216'

ELV. 1755 - FINISH DRITE 1189'

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ☒

Operations Completed: Hour: 6:15 AM Day: 23 RD Month: JULY Year: 1985

ACTUAL PLUGGING REPORT ORDERED 210 SK 60/40 POZ MIX GEL-CA-CL - AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - RECONDITION HOLE, HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 3175 FT 1/25 SK CMT, 2ND PLUG @ 1200 FT 1/25 SK CMT.3RD PLUG @ 660 FT 1/100 SK CMT, 4TH PLUG @ 240 FT 1/40 SK CMT.5TH PLUG SOLID BRIDGE HULLS - PLUG @ 40 FT 1/10 SK CMT. 10 IN RAT HOLE (CIRCULATE)

CEMENTED BY ALLIED CMT.

Remarks:

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 8-5-85

INV. NO. 9366

7-23

RECEIVED
STATE CORPORATION COMMISSION

Signed

AUG 5 1985

[Signature] (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KANSASFORM CP-2/3
Rev. 01-84