

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23332-00-00
Spot: E2E2SE Sec/Twnshp/Rge: 26-7S-18W
1200 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: HAZEN UNIT Well Number: 1
County: ROOKS Total Vertical Depth: 3483 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 252
Production: Size feet:
Liner: Size feet:

913.20

Well Type: DH UIC Docket No: Date/Time to Plug: 08/24/2001 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 225 sxs 60/40 pozmix - 6% gel.

Plugging Proposal Received By: ROGER MOSES
Date/Time Plugging Completed: 08/24/2001 3:00 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 252'.
1st. Plug at 3420' w/25 sxs cement. - Arbuckle
2nd. Plug at 1280' w/25 sxs cement - Anhydrite.
3rd. Plug at 760' w/100 sxs cement - Dakota.
4th. Plug at 300' w/40 sxs cement - Base Surface Pipe.
5th. Plug at 40' w/10 sxs cement.
15 sxs in rathole.
10 sxs in mousehole
Total of 225 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack.

RECEIVED
SEP 04 2001
KCC WICHITA

Remarks: LEASE READS AS FOLLOWS: 120'S.OF E2E2SE 26-07-18W. ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

INVOICED

DATE

9-4-01

INV#

2002560330

Form CP-2/3

AUG 29 2001