

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21, 906 ✓ 00-00
NE, Sec. 26, T 7 S, R 18 W/E
2310 feet from N/S section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076
Operator: Black Diamond Oil
Name & Address 217 E. 32nd, Hays, Mo. 67601

Lease Name Lawn Well # 1
County Neosho
Well Total Depth 3465 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8" feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Lambert Drilling Co. License Number 458

Address 289, Matoma, Mo. 67651

Company to plug at: Hour: 9:00 AM Day: 23 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO John Wise

(company name) Lambert Drilling Co. (phone) 913-885-4676

were: Order 180 sks 50% pozmix - 4% cel. - 3% cel. cl. & 8 5/8" plug.
Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 3460' w/
20 sks. 2nd plug @ 1325' w/ 20 sks. 3rd plug @ 750' w/ 80 sks.
4th plug @ 325' w/ 40 sks. 5th plug - solid bridge of plugs & plug
@ 40' w/ 10 sks, circulate 10 sks in rat hole.

Signed E. G. J. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 AM Day: 23 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT 9 5/8" 286' SP. cas. w/ 165 sks cement - 2% cel. - 3% cel. cl.

Ordered 180 sks 50% pozmix - 4% cel. - 3% cel. cl. & 8 5/8" plug. Spot w/ drill
stem w/ heavy mud between all plugs. 1st plug @ 3460' w/ 20 sks. 2nd
plug @ 1325' w/ 20 sks. 3rd plug 750' w/ 80 sks. 4th plug @ 325' w/ 40
sks. 5th plug - solid bridge of plugs & plug @ 40' w/ 10 sks.
Circulated 10 sks in rat hole.

Remarks: Drilled into Arbuckle

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~did~~ (did not) observe this plugging.

INVOICED

DATE 1-31-83

INV. NO. 2277-W

Rec'd 12-29-82

Signed E. G. J. [Signature]
(TECHNICIAN)