

6 010715

K 6-18

D-23,057  
Docket #23,057

100-00

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,259 - 00-00

NW NW SW SEC. 23, T 7 S, R 18 W/E

~~2970~~ 2310 feet from S section line

~~330~~ 4950 feet from E section line

Lease Name Alfalfa Plant Well # 1

County Rooks 115.60

Well Total Depth 3557 feet

Conductor Pipe: Size 13 3/8 feet 84 cwc

Surface Casing: Size feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 4585

Operator: C. F. Rupp

Name & Address 2804 Country Lane

Hays, Kansas 67601

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor C.F. Rupp License Number 4585

Address Same

Company to plug at: Hour: 10:00AM Day: 18 Month: June Year: 19 90

Plugging proposal received from Tim Lewin

(company name) Same (phone)

were: Run wireline for fluid level and t.d. Notify City Manager. City of Stockton, Ks. and Mr. Bruce Krob (farmer and offset landowner). Order 200 sks common cement 300 sks cement 65/35 poz 6% gel and 2 sks f.c. 5 1/2" casing at 3423 cwc. Open hole 3423-3557.

Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: Noon Day: 18 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Dennis Hamel witnessed wireline.

Fluid level at 800' and t.d. at 3445. Pumped down 5 1/2 casing 200 sks common cement and 300 sks 65/35 poz 6% gel. Max pres. 900#. Closed w/400#. Cement was to surf in 8 5/8. Checked June 22nd by Dennis Hamel. Cement was to surface.

RECEIVED STATE CORPORATION COMMISSION

JUL 12 1990

Remarks: Allied. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 7-17-90

INV. NO. 28617

SEP 14 1990

Signed Dale F. Balthazor Dennis L. Hamel (TECHNICIAN)

Dale F. Balthazor Dennis Hamel

FORM CP-2/3 Rev. 01-84