

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,190-00-0 0

NW-NW-NE Sec. 7, T 7 S, R 19 NE

330 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6041

Lease Name RIFFE Well # 2

Operator: PETROVENTURES, INC
Name & Address 165 S. UNION BLVD.
#670
LAKEMOOD, COLORADO
80228

County BOONIS

Well Total Depth 3565 feet 8115.86

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor DUNNE-GARDNER PET. INC License Number 5426 TAG # 193

Address SUITE 250 - 200 W. DOUGLAS, WICHITA, Mo. 67202

Company to plug at: Hour: 1:30 AM Day: 25th Month: Oct Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO FRANCIS ZINK

(company name) DUNNE + GARDNER PET INC (phone) 316-265-1611

were: 8 5/8" - 211^{ET} SB. CUL^W / 150^{SK} COMMON 2% GEL - 3% CA-CL. (BY ALLIED)

ORDER 200^{SK} 50^{SK} FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

ARRUCLES @ 3498^{ET}

Signed Francis Zink
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 AM Day: 25th Month: Oct Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 200^{SK} 50^{SK} FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS

1ST Plug @ 3480^{ET} 1/20^{SK} CNT., 2ND Plug @ 1560^{ET} 1/20^{SK} CNT.

3RD Plug @ 960^{ET} 1/100^{SK} CNT., 4TH Plug @ 240^{ET} 1/40^{SK} CNT.

5TH Plug ^{SOLID BRIDGE} MUDS Plug @ 40^{ET} 1/10^{SK} CNT., 10^{SK} RATABLE (CIRCULATE)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1983
CONSERVATION DIVISION
Wichita, Kansas
INVOICED
DATE 11-7-83
INV. NO. 6025-W

Signed Francis Zink
(TECHNICIAN) BOIC

10-31-83