

To: 6 031214  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-28  
API NUMBER 15-163-01312-00-00

SW SW SE , SEC. 5 , T 7 S, R 19 W/E  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Dryden Rifle Unit 2-3 #3

Operator: Graham Michaelis Corp

County Rooks 112.13

Name & Address Box 247

Well Total Depth 3450 feet

Wichita, Ks. 67201

Conductor Pipe: Size \_\_\_\_\_ feet

RECEIVED  
STATE CORPORATION COMMISSION  
Casing Division  
Input Well

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 28 Month: Dec Year: 19 88

Plugging proposal received from Millard

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8" set at 191' w/120 sks. 5 1/2" set at 3447' w/125 sks. Perfs 3157' - 3252'

Order sand and common cement. Pull pipe. Run wire to anhy. Order 200 sks 65/35 Poz 10% Gel 2% Dical 500# Hulls. Allied Cement Co. B and L Water Trucks.

11 18 1989  
1-18-89  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45PM Day: 28 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3100' w/5 sks common cement on sand w/bailer.

Shot at 1510'. Recovered 1479' of casing hole open to anhy. Squeezed 8 5/8" w/200 sks cementw/500# Hulls mixed into max psi 600#. Close in psi 300#. Plug complete.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Please serve this plugging.

DATE 1-19-89

INV. NO. 23689

Jed S.

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow