

4-070177

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,848 ⁻⁰⁰⁻⁰⁰

NW NW NW /4 SEC. 13, 07 S, 19 W
4950 feet from S section line
4950 feet from E section line

Operator license# 4580
Operator: Roy Farr Heirs
Address: 209 W. 33rd Street
Hays, Kansas 67601

5/30

Lease: Farr Well # 1
County: Rooks
Well total depth 3430 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 9 5/8 Inch @ 205 feet
W/125 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Roy Farr Heirs License# 4580

Address: 209 W. 33rd Street - Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 30 Month: May Year: 2000

Plugging proposal received from: Charlie Farr

Company: Roy Farr Heirs Phone: 785-628-2513

Were: 5 1/2" casing set at 3385' w/150 sxs.
Perfs at 3047' - 3290'. Bridge at 930'.
Ordered out 300 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 2000

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All , Part , None

CONSERVATION DIVISION
Wichita, Kansas
6-1-2000

Completed: Hour: 5:15 P.M. Day: 30, Month: May, Year: 2000

Actual plugging report: Ran 2 3/8" tubing to 930' - washed clean to 2450'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled to 800'.
Perforated at 1448' and 843'. Ran tubing back to 1500'. Allied pumped 110 sxs - 200# hulls - cement circulated. PTOH. Squeezed 6 sxs. Max. P.S.I. 500#. S.I.P. 400#.
Hooked-up to backside. Allied pumped 50 sxs with Max. P.S.I. 400#. S.I.P. 300#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1943 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED
DATE 6/7/00
NW, NO. 61833

R