

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,301 00-00

SE, Sec. 12, T 7 S, R 19 W/X
1650 feet from X/S section line
1650 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Farr Well # 1

Operator: Petroleum Inc.
Name & 300 W. Douglas
Address Wichita, Ks.

County Rooks

Well Total Depth 3380 feet 109.85

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 255

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center Building, Wichita, Ks.

Company to plug at: Hour: AM Day: 4 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Harold Maley

(company name) Abercrombie Drilling (phone) (913)674-5768

were: Ordered 185 sks cement 50/50 pozmix 6% gel 3% cal.cl. 1 sk hulls 1-8⁵/₈ plug
1 sk flow seal. Heavy mud between all plugs. Pump cement down drill pipe.

Elevation 1926 Anhydrite 1444-76 Arbuckle No Dakota 1400

Signed Ralf Baltazar
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:45 PM Day: 4 Month: March Year: 19 84

ACTUAL PLUGGING REPORT Circulated @ 1450 for 20 minutes

1st plug 25 sks @ 1450

2nd plug 100 sks @ 825 mixed with 1 sk flow seal

3rd plug 40 sks @ 300 1sk hulls push plug to 40

4th plug 10 sks @ 40

10 sks in Rat Hole

Cemented by: Halliburton
Remarks:

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1984

CONSERVATION DIVISION
Wichita, Kansas

3-12-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed Ralf Baltazar
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 3-13-84

INV. NO. 0739