

12-18

220
R

6-100446

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,189 ⁰⁰⁻⁰⁰

S/2 SE SW /4 SEC. 10, 07 S, 19 W
330 feet from S section line
3300 feet from E section line

Operator license# 5184 Lease Graham well # 2

Operator: Shields Oil Producers, Inc. County Rooks

Address: Shields Building Well total depth 3478 feet ^{113.03}
Russell, Kansas 67665 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Company License# 5655

Address: Russell, Kansas 67665

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1490 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 870 feet " 100 " Mousehole: 10 sacks

3rd plug @ 265 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx.

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:15 pm, Day: 18, Month: December, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 1973 GL, Anhydrite depth: 1491 - 1524 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied

INVOICED [] did not [X] observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

DATE 1-10-92

INV. NO. 34312