

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22, 184-00-00

TECHNICIAN'S PLUGGING REPORT

1950 feet from N/S section line
1950 feet from W/E section line

Operator License # 5428

Lease Name GRAHAM Well # 2

Operator: GRAVES DRILLING Co, INC.
Name &
Address 910 UNION CENTER
WICHITA, Mo
67202

County ROOFS
Well Total Depth 3580 feet 113.75
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor RED TIGER DRILLING License Number 5302

Address 1720 N.S.B. & T. BLDG. WICHITA, KANS. 67202

Company to plug at: Hour: 2:00 PM Day: 25th Month: Oct Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO SAM MAGNER

(company name) RED TIGER DRILLING (phone) 316-263-2371

were: 8 5/8" 248' 5/8" CUL 1/160 SK COMMON-2% GEL-3% CA-CL. (BY ALLIED)
ORDER 180 SK 2/50 Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS
NO AIRBUCKLE

Signed [Signature]
(TECHNICIAN) 801C

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 PM Day: 25th Month: Oct Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 180 SK 2/50 Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS
1st Plug @ 1530 FT 1/20 SK CNT -> 2nd Plug @ 880 FT 1/100 SK CNT
3rd Plug @ 270 FT 1/40 SK CNT, 4th Plug SOLID BRIDGE @ 40 FT 1/10 SK CNT
10 SK IN RAT HOLE (CIRCULATES) (CEMENTED BY ALLIED CNT)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not observe this plugging.

INVOICE
DATE 11-7-83
INV. NO. 6008-1
RECEIVED
OCT 31 1983
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN) 801C

10-31-83