

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER 15-163-21,269-00-00 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER Cherokee Petroleum Corp.

ADDRESS 410 17th St., Suite 2300, Denver, CO 80202

LEASE (FARM NAME) GRIEBEL WELL NO. 2

WELL LOCATION NE NW NE SEC. 5 TWP. 7S RGE. 19W (EAST) (WEST)

COUNTY Rooks TOTAL DEPTH 3555' FIELD NAME _____

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A XX

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:00 a.m., 7/24/81.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wilmer Dreiling (Toolpusher) ADDRESS 408 Jefferson, Ellis, KS, 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. _____

ADDRESS 801 Union Center, Wichita, KS 67202

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Cherokee Petroleum Corp.

ADDRESS 410 17th St., Suite 2300, Denver, CO 80202

AND PAYMENT WILL BE GUARANTEED BY APPROVAL OF ACTING AGENT.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1981
CONSERVATION DIVISION
Wichita, Kansas
7-29-81

SIGNED: Jack L. Partridge

APPLICANT OR ACTING AGENT

Jack L. Partridge, Vice President

DATE: July 27, 1981

15-163-21269-00-00

CONTRACTORS WELL LOG

OPERATOR:	Cherokee Petroleum Corp.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	GRIEBEL #2
LOCATION:	NE NW NE, Sec. 5-7S-19W Rooks County, Kansas
SPUD DATE:	7/16/81
COMPLETION DATE:	7/24/81

0	1575	Sand & Shale
1575	1615	Anhydrite
1615	2463	Shale
2463	2609	Shale & Lime
2609	2953	Shale
2953	3258	Shale & Lime
3258	3365	Lime
3365	3525	Shale & Lime
3525	3535	Lime
3535	3555	Shale & Lime
	3555	Rotary Total Depth

Spud hole @ 1:30 p.m., 7/16/81. Drilled 230' of a 12 1/4" hole. Ran 5 joints of 8 5/8" 24# casing set @ 226'. Cemented with 150 sacks of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 11:30 p.m., 7/16/81.

3555' RTD. Set 1st plug @ 840' with 65 sacks. Set 2nd plug @ 200' with 30 sacks. Set 3rd plug @ 40' Solid Bridge with 10 sacks. 5 sacks in Rathole. Job complete @ 1:00 a.m., 7/24/81.

SAMPLE TOPS:

Anhydrite 1575' - 1624'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GRIEBEL #2, NE NW NE, Sec. 5-7S-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.


Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 27th day of July, 1981.

Elizabeth G. Terry
Elizabeth G. Terry
NOTARY PUBLIC

my commission expires 7-13-81

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1981
7-29-81
CONSERVATION DIVISION
Wichita, Kansas



STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

September 25, 1981

INVOICE NUMBER: 7513-W

TO: Cherokee Petroleum Company
410 17 th St.
2300
Denver CO., 80202

15-163-21269-0000

PAYABLE UPON RECEIPT

PLUGGING ASSESSMENT AS FOLLOWS:

~~XXXXXX~~ ^{XX}

Griebel #2 \$115.57
230' W NE NW NE, Sec.5-7S-19W

NOTE: We also need the following before our file is completed:

- Books
- 3556'
- Well Plugging Record (CP-4)
- Well Log
- Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

For Administrator



Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601
is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE