

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 103 - 20894 - 00 - 00 (of this well)  
Lease Owner Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Graham Well No. 1  
Well Location C NW SW SW Sec. 10 Twp. 7S Rge. 19W (E)      (W) x  
County Rooks Total Depth 3490' Field Name       
Oil Well      Gas Well      Input Well      SWD Well      Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 1:15 a.m., 2-28-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Leon Strecker Address 223 10th Street, Wakeeney, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.     

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: *Jack L. Partridge*  
Applicant or Acting Agent

Jack L. Partridge

Date: March 5, 1979

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 7 1979  
3-7-79  
CONSERVATION DIVISION  
Wichita, Kansas

FEB 23 1979

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

**KANSAS DRILLERS LOG**


S. 10 T. 7 R. 19 <sup>R</sup>/<sub>W</sub>

API No. 15 — 163 — 20,894 <sup>00-00</sup>  
County Number

Loc. NW SW SW

County Rooks

640 Acres



Locate well correctly

Elev.: Gr. 1962'

DF 1965' KB 1967'

Operator <b>Abercrombie Drilling, Inc.</b>	
Address <b>801 Union Center Wichita, Kansas 67202</b>	
Well No. <b>#1</b>	Lease Name <b>Graham</b>
Footage Location  feet from (N) (S) line _____ feet from (E) (W) line _____	
Principal Contractor <b>Abercrombie Drilling, Inc</b>	Geologist <b>William Darrow</b>
Spud Date <b>February 18, 1979</b>	Total Depth <b>3490'</b>
Date Completed <b>February 28, 1979</b>	P.B.T.D.
	Oil Purchaser

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	220'	common	150	3% Ca. Cl. 2% gel.

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used

STATE CORPORATION COMMISSION  
 RECEIVED  
 FEB - 7 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 3-7-79

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
**Abercrombie Drilling, Inc.**

DESIGNATE TYPE OF COMP.: OIL, GAS,  
 DRY HOLE, SWDW, ETC.:  
**Dry Hole**

Well No. 1 Lease Name Graham

S 10 T 7S R 19WE  
W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	222	<u>SAMPLE TOPS:</u>	
Shale	222	425	Anhydrite	1485' (+ 482)
Sand and shale	425	1428	B/Anhydrite	1513' (+ 454)
Shale	1428	1485	Topeka	2923' (- 956)
Anhydrite	1485	1513	Heebner	3123' (-1156)
Shale	1513	2773	Toronto	3145' (-1178)
Shale and lime	2773	2970	Lansing	3164' (-1197)
Shale	2970	3120		
Lime	3120	3460		
Shale	3460	3490		
Rotary Total Depth		3490		
			<u>ELECTRIC LOG TOPS:</u>	
DST #1 (3093-3120') 30", 45", 60", 45"			Anhydrite	1481' (+ 486)
Fair blow. Rec. 150' mdy wtr.			B/Anhydrite	1510' (+ 457)
IFP 20-30, IBHP 1020, FFP 41-61, FBHP 938			Topeka	2917' (- 950)
Temp. 100°			Heebner	3117' (-1150)
DST #2 (3130-3160') 30", 30", 30", 30"			Toronto	3145' (-1178)
Weak blow 10" died. Rec. 10' mud			Lansing	3160' (-1193)
IFP 20-20, IBHP 20, FFP 20-20, FBHP 20			B/KC	3380' (-1413)
DST #3 (3130-3180') 30", 45", 30", 30"			Arbuckle	3448' (-1481)
Rec. 30' mud.			LTD	3487'
IFP 40-40, IBHP 92, FFP 51-51, FBHP 61			DTD	3490'
DST #4 (3307-3334') 30", 45", 30", 30"				
Weak blow 10" died. Rec. 20' ocm, 10% oil.				
IFP 20-20, IBHP 153, FFP 30-30, FBHP 41				
DST #5 (3342-3388') 30", 30", 30", 30"				
Rec. 10' osm				
IFP 30-30, IBHP 489, FFP 40-40, FBHP 326				
Temp. 104°				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_

Signature Jack L. Partridge

Jack L. Partridge, Asst. Sec.-Treas.

Title

March 5, 1979

Date

State of Kansas



15-163-20894-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

March 1, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Graham
Description	NW SW SW Sec. 10-7-19W
County	Rooks
Total Depth	3490
Plugging Contractor	Co. Tools


Abercrombie Drilling, Inc.  
801 Union Center  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above  
named well.