

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1977
7-6-77

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,717 - 00-00 (of this well)

Operator's Full Name Rim Oil Company

Complete Address 512 S. Wyoming, Plainville, Kansas 67663

Lease Name K. U. Endowment Assoc. Well No. 1

Location SE SE NE Sec. 25 Twp. 7 Rge. (E) (W) 18

County Rooks Total Depth 3390'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 7:45 A Day 3 Month 7 Year 1977

The above well was plugged as follows:

RTD 3390' 8 5/8 csg set 215' cwc 160 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 450' thru drill pipe.

heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-6-77
INV. NO. 5441-C

Signed: B. E. Murrain
Well Plugging Supervisor