

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20095-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas
6-21-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Midwestern Supply Company, Incorporated,

Complete Address 207 Brown Building, Wichita, Kansas.

Lease Name Maddy Well No. 1

Location NW-NW-SW Sec. 36 Twp. 7 Rge. (E) (W)18

County Rooks Total Depth 3383'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 2:30 PM Day 16 Month 6 Year 1971

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 140 Sx.
3365'--4 1/2" production casing cemented on bottom with 100 Sx. Bridge plug set above top perforations. Well flowing from break-in in Dakota.

Squeezed 4 1/2" casing initially with 5 sacks hulls and followed with 25 sacks gel then 60 sacks cement. Maximum pump-in pressure-350#. Final shut-in pressure-150#.

Squeezed annulus with 100 Sx. cement, maximum pump-in pressure-100#. Final shut-in pressure-50#. Mudding and cementing operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/22/71
INV. NO. 3891-W