

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20093-00-00

JAN 2 1968
1-2-68

Operator's Full Name Mark Richardson

Complete Address 502 Union Center Bldg., Wichita, Kansas

Lease Name Maddy Well No. 1

Location SE SE SW Sec. 35 Twp. 7 Rge. 18 (E) (W) X

County Rooks Total Depth 3470

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 2 A Day 30 Month 12 Year 1967

The above well was plugged as follows:

RTD 3470' 8 5/8 csg set at 206' cwc 140 sc. Cementing Material 50-50 Poz W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10' sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reo F. Massey
Well Plugging Supervisor

DATE 1-3-68

INV. NO. 7029-W