

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00457-06-01

RECEIVED  
STATE CORPORATION COMMISSION

MAR 11 1970

CONSERVATION DIVISION  
Wichita, Kansas

3-11-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name J. Mark Richardson

Complete Address 502 Union Center Wichita, Kansas 67202

Lease Name Roelfs Well No. 1

Location SE SW NE Sec. 35 Twp. 7 Rge. (E) (W) 18

County Rooks Total Depth 3398

Abandoned Oil Well XXX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11:30A Day 7 Month 3 Year 1970

The above well was plugged as follows:

Total Depth 3398' 8 5/8 csg set at 203' cwc 150 sk.

4 1/2 csg set at 3397' cw 100 sk cmt.

4 1/2 csg PBTD 3397 1/4 with top perf. (3355)

Filled 4 1/2 csg W/sd (3340-3397 1/2) Dumped 4 sk cmt W/dump bailer. (3300-3340)

Cutoff and recovered 2000' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 17 sk gel / 5 sk hulls, 70 sk poz 6% gel,

8 sk gel, plug and 50 sk poz 6% gel.

Cmt. (0-200) gel (200-500) Cmt 500-700) Gel & hulls (700-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey  
Well Plugging Supervisor

DATE 3/11/70  
INV. NO. 1572-W