

15-163-20421-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Drilling Company Inc. & Woodman- Iannitti Drilling

Complete Address 800 Bitting Bldg., Wichita, Kansas

Lease Name Albright Well No. 1

Location NE NE SE Sec. 36 Twp. 7 Rge. (E) (W) 18

County Rooks Total Depth 3445'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10:30 P Day 7 Month 3 Year 1972

The above well was plugged as follows:

RTD 3445' 8 5/8 csg set at 220' cwc: Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-10-72

INV. NO. 5327-W

Signed: Rep. J. Massery
Well Plugging Supervisor