

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT
13-163-20320--00-00
RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

8-19-70

Operator's Full Name Murfin Drilling Company
Complete Address 617 Union Center, Wichita, Kansas 67202
Lease Name Riffe Well No. # 1
Location SE SE NE Sec. 7 Twp. 7 Rge. 19 (E) (W) W
County Rooks Total Depth 3550
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated _____
Plugging Contractor Same (Co. tools)
Address Same License No. _____
Operation Completed: Hour 9:30 P.M. Day 15 Month 8 Year 1970

The above well was plugged as follows:

8 5/8" 206' Cwc.

Circulated hole with heavy mud to 750', set plug, & displaced 50 sax cement thru
drill pipe. Mud to 200' & displaced 20 sax cement thru drill pipe. Mud to 40',
1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing Company's pump
truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Luman
Well Plugging Supervisor

INDEXED
8/19/70
2411-W