

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-30014-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1965
4-9-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John Ostmeyer

Complete Address: c/o Leo J. Dreiling Victoria, Kans

Lease Name Smith Well No. 1

Location SW SW NE Sec. 6 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3567

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 3PM Day 6 Month 4 Year 65

The Above well was plugged as follows:

8 5/8" 155' circulated with cement - 5 1/2" 3558' PB to 3522' Perf 3300'
Set plug at 3280', sand back and set 4 sax cement with dump bailer - pulled
2390' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2" at 600'
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 250', displaced
20 sax cement through 5 1/2" at 250', heavy mud to 35', cement to bottom
cellar.

Mudding and cementing by Ace pipe pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edwin Petty
Well Plugging Supervisor

DATE 4/9/65
INV. NO. 958-W