

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-213 08-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Russell Supply Co. Inc

Complete Address P.O. Box 73 - Russell, Kansas 67655

Lease Name Stice Well No. 1

Location NW 4 Sec. 6 Twp. 7 Rge. 19 (East) (West)

County Rooks Total Depth 3575

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sun Cementing - Baker Oil Well Service

Address Hays, Kansas Codell, Kansas License No. _____

Operation Completed: Hour: 4:00pm Day: 10 Month: 3 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Well record provided by Mr. Virgil Hagan
8 5/8" set @ 300' w/ 225 sv (8 5/8" set @ 200'/150 sv) - 5 1/2" set @ 3669' w/ 150 sv
Open hole 3569-75 - Top perf 2310' - No plug back - Recovered
1700' of 5 1/2" casing (L-K Wireline Hays, Ks) Mr. Hagan was
instructed to run tubing to approximately 1800' but
failed to do so. Mr. Hagan pumped into 8 5/8" surface casing ->
3 hulls -> 13 gal -> 50 emt -> 6 bbls water -> 20 gal -> 200 emt -> 6 gal ->
2 hulls -> 50 emt. -> max p.s.i. 600# -> shut in 250# p.s.i.
(emt. by Sun)
'Red'

Amount of Surface Casing: 300'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Mr. Hagan was to call Marion Schmitt or me prior
to cementing but failed to call - a message was left at

Northwestern Pump & Supply with my wife that the Stice Well was
to be plugged @ 1:30 p.m. - Signed: Dennis L. Hamel
I received the message @ 1:30 & Conservation Division Agent
drove directly to location - Plugging
was underway - (at 20 gal) bal of
plugging witnessed by me.

DATE 3-26-82
INV. NO. 9778-W
RECEIVED
STATE CORPORATION COMMISSION
3-23-82
MAR 23 1982
CONSERVATION DIVISION
Wichita Kansas

(9:30 AM)
3-16