

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

13-163-20300-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

4-6-70

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name ~~Regan~~ O' Reagan Well No. 1

Location SW NE SE Sec. 6 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3645

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 8:30P Day XX 1 Month 4 Year 1970

The above well was plugged as follows:  
RTD 3645' 8 5/8 csg set at 195' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing  
Well Plugging Supervisor

DATE 4/7/70

INV. NO. 1688-W