

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-1907.5-00-01

RECEIVED
STATE CORPORATION COMMISSION
FEP 5 1969
CONSERVATION DIVISION
Wichita, Kansas

2-5-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Western Oil Field Service

Complete Address: Box 163 Great Bend, Kansas 67530

Lease Name Hance (OWWO) Well No. 1

Location NW SW NE Sec. 31 Twp. 7 Rge. 18 (E) (W) XX

County Rooks Total Depth 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: (OWWO)

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30P Day 3 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 3410' 8 5/8 csg set at 1298' cwc

4 1/2 csg set at 3408' cw 150 sk cmt.

4 1/2 csg PBTB 3381' with top perf. 2943'

Set plug at 2900' Poured 10' sd and dumped 4 sk cmt with dump bailer.

Cutoff and recov. 2426' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 10 sk gel W/3 sk hulls, plug and 130 sk 50-50 poz cement with 6% total gel. Max. pres. 600 lbs. SI pres 600 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Bo F. Massey*
Well Plugging Supervisor

DATE *2/6/69*

INV. NO. *9285-u*