

DISTRICT CONSERVATION AGENT'S REPORT

15-163-02999-00-01

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NWCNW NE
SEC. 9 TWP. 7 RGE. 19W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Desmarteau

Operator Magnolia Pet Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3508 Feet.

Plugging Contractor Ave Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 190' circulated with cement - 6 5/8" at 3508'

with 200 sax cement behind - P.B. to 3387', perforated at 3262'.

Sand to 3250', set 4 sax cement with dump bailer, pulled 2500'

6 5/8", heavy mud to 185', set rock and 20 sax cement, mud to 30'

set rock and 10 sax cement to bottom cellar.

E. J. Petty

District Conservation Agent

7-10-56

Date _____

PLUGGING
FILE SEC. 9 T. 7 R. 19W
BOOK PAGE 80 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
DIVISION OF CONSERVATION

17-16-56