

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-163-02710-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 126-43LOCATION NW NE NWSEC. 9 TWP. 7 RGE. 19WDry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease DesmarteauOperator Sierra Pet Inc Address 420 West Douglas WichitaField _____ County RooksTotal Depth 3479 Feet.Plugging Contractor Forbes Casing Pulling & Sun Cementing CoPlugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 205' circulated with cement - 5 1/2" at 3476' with 50
sax cement behind.

Spotted 5 sax cement on bottom with dump bailer - pulled 2115' 5 1/2" -
pumped hole full mud (40 sax Gel), pumped cementing plug to
200' followed by 65 sax cement - Cement 200' to 0'
Cementing by Sun Cementing Co - 250# pump pressure.

RECEIVED	
STATE CORPORATION COMMISSION	
PLUGGING	
FILE	SEC <u>9</u> T <u>7</u> R <u>19W</u>
BOOK	PAGE <u>126</u> LINE <u>43</u>
CONSERVATION DIVISION	
Wichita, Kansas	

E. J. Letty
District Conservation AgentDate 1-1-57