

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,884-00-00 (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Ks.

Lease Name Farr Well No. 2

Location SE NW NW Sec. 13 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3415'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Pioneer Drlg.

Address P-Ville, Ks. License No.

Operation Completed: Hour 4 P Day 28 Month 1 Year 1979

The above well was plugged as follows:

RTD 3415' 8 5/8 csg set 211' cwc 140 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

STATE CORPORATION COMMISSION

JAN 30 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

1-30-79

INVOICED

DATE 1-30-79

INV. NO. 9018-W

Signed: Geo Massey
Well Plugging Supervisor