

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 163-20880-00-00 (of this well)
6-29-79

Operator's Full Name LIBERTY ENTERPRISES, INC.
Complete Address 308 WEST MILL PLAINVILLE, KS. 67663
Lease Name HUNTER Well No. #1
Location NW-NE-SW Sec. 13 Twp. 7 Rge. 19(E) (W) N
County ROOKS Total Depth 2430 FE
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor KELSO CASING PULLING
Address BOX 176 CHASE, KS. 67524 License No. 683
Operation Completed: Hour 11:30 AM Day 28th Month JUNE Year 1979

The above well was plugged as follows:

8 5/8" 216^{FE} S.P. cve 150ST COMMON 2% GEL. - 4 1/2" 3264^{FE}
cve. 100ST COMMON 50ST 50/50 Pozmix 10% SAULT. T.D. 3234^{FE}
OPEN HOLE - PLUG BACK 3100^{FE} WITH SAND AND 4ST CMT.
SHOT PIPE AT 2134^{FE} RECOVERED 2134^{FE}
ORDERED 135ST 50/50 POZMIX 6% GEL (PUMPED IN WITH PUMP TRUCK)
15ST GEL AND 2ST HULL'S.
PUT IN - 1 HULL - 7 GEL - 70 CMT. - 8 GEL - 1 HULL
RELEASE PLUG. AND 65ST CMT. - MAX PRESSURE 500^{PSI} TO 0 -

I hereby certify that the above well was plugged as herein stated.

ALLIED CEMENTING

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 7-2-79
INV. NO. 9932-W