

4-041773

15-163-19164-00-00

D-08,811

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

6-4

API Number: 15- -

90' N.C. of
N2 SW NE /4 SEC. 18, 07 S, 20 W
3720 feet from S section line
1980 feet from E section line

Operator license# 6931

Lease: Lesage Well # 4

Operator: Bowman Oil Company

County: Rooks

Address: 805 Codell Road
Codell, Kansas 67663

Well total depth 1435 46.63 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 0 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 4 Month: June Year: 1996

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone:

Were: 4 1/2" casing set at 1435' w/200 sxs cement. Perf. at 1255' - 1346'.
Ordered 100 sxs. 60/40 pozmix -10% gel - with 1/4# F.C. plus 300# hulls.

KANSAS RECEIVED
JUN 24 1996
6:06 PM

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 4, Month: June, Year: 1996

Actual plugging report: R.I.H. with tubing to 1200'. R.U. Cementers to circulate cement to surface with 90 sxs cement plus 300# hulls in cement. P.O.O.H. with tubing - squeezed 4 1/2" casing with 10 sxs cement. Max. P.S.I. 200#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

JUN 24 1996

DATE

45852

AUG 20 1996

6-4