

6 010628

309

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-21,487-00-00  
SW \_\_\_\_\_, SEC. 19, T 7 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8932

Operator: Apache Corp  
Name & Address: One United Bk Center  
1700 Lincoln St  
Denver, Colorado

330 feet from S section line  
330 feet from E section line

Lease Name Hutton Well # A-1  
County Rooks 106.21

Well Total Depth 3268 feet  
Conductor Pipe: Size 13 3/8 feet 80  
Surface Casing: Size 8 5/8 feet 1127

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Same as above License Number \_\_\_\_\_

Address Same

Company to plug at: Hour: 9:00AM Day: 19 Month: August Year: 19 88

Plugging proposal received from Roland Hyp

(company name) Apache (phone) \_\_\_\_\_

were: Pulled 3064' of 2 1/2" tubing casing open.

5 1/2" at 3232'. Anhydrite 1124' Elevation 1745'. SLD: 1450' - Top 295' 8 5/8" cemented  
w/400 sks 50/50. Order 500 sks cement 60/40 Poz 8% Gel and 400# Hulls.

Plugging Proposal Received by D. F. B.

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 19 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Pumped on 8 5/8" 600# pressure holding.

Pumped down 5 1/2" casing 300 sks cement w/300# Hulls.

Max pressure 1000# Holding 900#.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1988  
9-1-88

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cement Co. checked plug Aug 23, 1988. O.K. to top.  
(If additional description is necessary, use BACK of this form.)

do not discontinue observe this plugging.

INVOICED

DATE 9-7-88

INV. NO. 22132

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor