

6 070402

API NUMBER 15-163-22, 772-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE-NE-NE, SEC. 6, T. 7 S, R. 20 W

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7419

Operator: Alcona Del Company

Name & Address: 2908 Hillcrest Drive  
Hays, Kansas

67601

Lease Name Le Sage Well # D-#1

County (Rooks) 120.74

Well Total Depth 3715 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated Tag #256

Plugging Contractor Pioneer Drilling Inc License Number 5665

Address Plainville, Kansas, 67663

Company to plug at: Hour: 7:30 AM Day: 19th Month: Oct Year: 1985

Plugging proposal received from Tom Alm

(company name) Pioneer Drilling Inc (phone) 913-628-2899

were: 8 5/8" - 269' ES. CUC w/160 SK 60/40 Pozmix 2% Cel - By allied cont

Order 220 SK 60/40 Pozmix 6% 3% - 1 SK Cello and 8 5/8" Plug

spk with Drill Stem, Recondition Hole (viscosity) Heavy Mud between Plug

Arbuckle 3660' Elv. 2209, Only 1804 (No Circulation Problems)

Mud Condition 9.5 Weight, 44 Viscosity.

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent AM All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:30 AM Day: 19th Month: Oct Year: 1985

ACTUAL PLUGGING REPORT Ordered 220 SK 60/40 Pozmix 6% 3% - 1 SK Cello and 8 5/8" Plug

Spk with Drill Stem, Reconditioned Well. Heavy Mud between all Plugs

1st Plug @ 3660' w/25 SK cont, 2nd Plug @ 1830' Elv w/25 SK cont. SK

3rd Plug @ 1110' Elv w/100 SK cont w/2 Cello, 4th Plug @ 270' Elv w/20 cont

5th Plug Solid Bridge @ 40 ft to 0 w/10 SK cont.

10 SK In Pat Hole (circulate) Cemented By allied cont

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE NOV 12 1985

NOV 4 11-04-1985 Signed [Signature] (TECHNICIAN)

INV. NO. 10940

DEC 13 1985 CONSERVATION DIVISION Wichita, Kansas