

6010162

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163- 22414-00-00

NW, SEC. 5, T 7 S, R 20 W

990 feet from N/W section line

990 feet from W/W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Lease Name Lesage, Well # 1

Operator: J.B. Collins

County Rooks

Name & Address 1007 Cody

Well Total Depth 3735 121.39 feet

Hays Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Jay-Lan License Number 5128

Address 207 W. 12th Hays Ks.

Company to plug at: Hour: 4 PM Day: 6 Month: 7 Year: 19 84

Plugging proposal received from John Tremblay

(company name) Jay-Lan (phone) _____

were: order 185 5x cement 50/50 permix 6% gel. 3% c.c.

1- 5x hulls 1- 8 5/8 plug 1- 5x Flow Seal.

Pump cement down drill pipe.

Heavy mud between all plugs.

Elev. 2248 Anhydrite 1850-91 Arbuckle Np.

Dakota 1400 Plugging Proposal Received by Dale Batthazor

848 = 1150

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:30 PM Day: 6 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1860 for 15 mi.

25 5x @ 1860

100 5x @ 1150 mixed with 1 5x flow seal.

40 5x @ 350 Dumped 1 5x hulls pushed plug to 40'

10 5x @ 40

10 5x in Rat Hole

Remarks: cementing co. Allied.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
07-16-1984
JUL 16 1984

(did) did not) observe this plugging

INVOICED

DATE 7-24-84

INV. NO. 2611

Signed Dale Batthazor (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

July 13
4