

6 010239

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22544-00-00

SE, SEC. 4, T. 7 S, R. 20 W/4

330 feet from ^N N/S section line

990 feet from ^W W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Lease Name Wiens Well # 2

Operator: Black Diamond Oil

County Rooks

Name & Address 1105 E. 30th

Well Total Depth 3661 118.98 feet

Hays Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor R. & C. Drilg. Co. License Number 9087

Address Box 296. Hays Ks.

Company to plug at: Hour: PM Day: 7 Month: 11 Year: 19 84

Plugging proposal received from John Wise

(company name) R. & C. Drilg. Co. (phone) _____

were: order 210 sx. cm. 50/50 polymix 6% gel. 3% c.c.

Pump cem. down drill pipe 1-8 5/8 plug-1sx. flow seal

Heavy mud between all plugs.

Elev-2151 Anhydrite 1725-59 Arbuckle 3618

Dakota-1400 Plugging Proposal Received by Dale F. Balthazor

751 = 1050

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ (None)

Operations Completed: Hour: 12:15 AM Day: 8 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3620 for 45 mi.

25 SX @ 3620

25 SX @ 1730

100 SX @ 1050 mixed w/ 1 sx. Flow Seal

40 SX @ 250

10 SX @ 40 on Solid Bridge

Remarks: 10 SX in Rat Hole Allied cementing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

11-15-84

Signed Dale F. Balthazor
(TECHNICIAN)

4772

RECEIVED
STATE CORPORATION COMMISSION
11-13-1984
NOV 13 1984
CONSERVATION DIVISION
Wichita, Kansas

11-9-84
9