

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22238-00-00

NW 1/4 SEC. 19, T. 7S, R. 17W

2310 FEET FROM N/S SECTION LINE

1650 FEET FROM W/S SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 8932

LEASE NAME Hutton WELL # 5

OPERATOR: Apache Corporation  
NAME &  
ADDRESS 1660 Lincoln St. Suite 2300  
Denver, Colorado 80264

COUNTY Reeds

WELL TOTAL DEPTH 3320' 107.90 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8" FEET 1186

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Ranger Drilling LICENSE NUMBER \_\_\_\_\_

ADDRESS Box 856, 1006 Canterbury Rd., Hays, Kansas 67601

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YEAR: 19 \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM Frank Taggart

(COMPANY NAME) Ranger Drilling (PHONE) \_\_\_\_\_

WERE: 1st plug @ 3250' with 20 sacks Rathole - 10 3x

2nd " " 1200' " 40 "

3rd " " 580' " 80 "

4th " " 40' " 10 " solid bridge plug

order 160 sx 50/50 posmix, 4% gel, 3% CC.

PLUGGING PROPOSAL RECEIVED BY \_\_\_\_\_ (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: 5:30pm DAY: 31 MONTH: Dec YEAR: 19 83

ACTUAL PLUGGING REPORT \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

REMARKS: Elevation: 1753 KB., Anhydrite depth: 1172-1211'

did penetrate Anbuckle, cemented by Sun

\_\_\_\_\_  
\_\_\_\_\_

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED David Kuwann  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1984  
1-16-84  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 1-18-84  
INV. NO. 9122 W

FORM CP-2/3  
5 REV. 6-83