

4-042009

3-22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-21,300-00-00  
100' S. of  
C SE SW / 4 SEC. 07, 07 S, 20 W  
560 feet from S section line  
3300 feet from E section line

Operator license# 31008

Lease: LeSage Well # 1

Operator: Paul Bowman Oil

County: Rooks 118.63

Address: 801 Codell Road  
Plainville, Kansas 67663

Well total depth 3650 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 242 Feet  
W/N/A sxs.cmt.

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 22 Month: March Year 1999

Plugging proposal received from: Paul Bowman

Company: Paul Bowman Oil Phone: -

Were: Ordered 175 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
4 1/2" casing set at 3639' w/150 sxs cement.  
Perfs at 3402' - 3601'.  
Casing squeezed at 800' w/150 sxs cement.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[    ], Part[ X ], None[    ]

Completed: Hour: 10:45 A.M., Day: 22, Month: March, Year: 1999

Actual plugging report: R.I.H. with tubing to 2100'. Spotted 50 sxs with 300# hulls. Pulled to 1050'. Spotted 50 sxs cement with 200# hulls. Circulated at surface. P.O.O.H. with tubing, squeezed casing with 75 sxs cement to 200# P.S.I.  
Hooked-up to 8 5/8" S.P. Squeezed 10 sxs cement down annulus to 400# P.S.I.

Remarks:     

Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING      CASING X. Elevation:      G.L.

I did[ X ] / did not[    ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
APR - 7 1999  
04-07-1999  
CONSERVATION DIVISION  
Wichita Kansas

INVOICED

DATE 4-8-99

INV. NO. 60803

3-22