

6-4-88

6 031100

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,970-00-00
(SE NE NW) 4S.
C S 1/2 N 1/2 NW SEC. 6, T 7 S, R 20 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

Operator: PanCanadian Pet Co.
Name & Address: Box 929
Denver, Colorado 80201

4290 feet from S section line

3980 (2970) feet from E section line

Lease Name Waller Well # 2

County Rooks 122.88

Well Total Depth 3781 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Pulled within 120 days, Alt. #2. Parameters

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 4 Month: June Year: 19 88

Plugging proposal received from Garr Roberts

(company name) PanCanadian (phone)

were: 8 5/8" set at 314' w/10 sks. 4 1/2" set at 3780' w/195 sks. PBDT 3681'.

Perf 3546' - 3639'. Order Common Cement. Phll pipe, Order 200 sks Cement Blend,

5 sks Hulls. B. J. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30AM Day: 4 Month: June Year: 19 88

ACTUAL PLUGGING REPORT CTBP at 3440' w/4 sks Common Cement on plug

w/bailer. One shot recovered 2480' of 4 1/2" casing. Squeezed 8 5/8" w/200 sks Cement Blend

w/5 sks Hulls mixed in. To max Psi 300#. Close in Psi 150#. Plug complete

RECEIVED
STATE CORPORATION COMMISSION
06-20-1988
JUN 20 1988

Remarks: CONSERVATION DIVISION
Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-30-88

INV. NO. 21136

Signed Carl Goodrow
(TECHNICIAN)