

6 050360

12-2-87

API NUMBER 15- . 163-22,963-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NE, SEC. 6, T 7 S, R 20 W/E

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Dean Lesage Well # 1

Operator: Ritchie Exploration

County Rooks 121.71

Name & Address 125 North Market Suite 1000

Well Total Depth 3745 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, Kansas

Company to plug at: Hour: AM Day: 1 Month: Dec Year: 19 87

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Co. (phone)

were: Order 205 sks 60/40 Pozmix 6% Gel 3% Cal Cl 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 9:45AM Day: 2 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 3712, Arb w/20 sks Witnessed in part by Dale Balthazor

2nd plug at 1840' w/20 sks

3rd plug at 1140' w/100 sks 1 sk Flocele

4th plug at 240' w/40 sks

5th plug at 40' w/8 5/8" w/10 sks

STATE CORPORATION COMMISSION

DEC 13 1987

12-11-1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: 15 sks in rat hole. Cemented by Allied

(if additional description is necessary, use BACK of this form.)

INVOICED

(did / did not observe this plugging.)

DATE 12-14-87

Signed Gilbert P. Leiker

(TECHNICIAN)
Gilbert P. Leiker

INV. NO. 19275