

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-21, 864 ⁰⁰⁻⁰⁰

LEASE NAME Riffe

WELL NUMBER 1

330 Ft. from S Section Line

4,620 Ft. from E Section Line

SEC. 6 TWP. 7 RGE. 19 (X or W)

COUNTY Rooks

Date Well Completed 12/82

Plugging Commenced 3/86

Plugging Completed 4/86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 E 30th, Hays, Ks. 67601

PHONE# (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - 1014 Cody - Hays, Ks. 67601

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation K.C. & ARB. Depth to Top 3,134 Bottom 3,602 T.D. 3,645

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota Sand	water	0	305	8 5/8	305	0
Cedar Hill	Water	0	3,648	4 1/2	3648	895
Topeka	oil & Water					
L.K.C.	oil & water					
Arbuckle	oil & water					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted sand from T.D. up to 3,000' - spotted 4 sacks of cement on top of sand with dump bailer - perforated 4 1/2" at 1,650' with 3 holes - cut off 4 1/2" at 895' and pulled - pumped 175 sacks of 60/40 Poz. with 10% Gel. and 2% light down 8 5/8" + 400# of Hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____


Address Russell, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.

Black Diamond Oil, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Siray Berland
 (Address) 1105 E. 30th, Hays, Ks. 67601

STATE CORPORATION COMMISSION
 APR 22 1986
 SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 86



Conservation Division
 Wichita, Kansas
 Commission Expires: 5/24/87
 Notary Public Philip C Toepfer