

API NUMBER 15-163-22182-00-00
LEASE NAME Carpenter
WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

Charley Farr

2310 Ft. from (S) Line of Section (circle one)
1650 Ft. from (E) Line of Section (circle one)

Byron Carpenter (Landowner)

LEASE OPERATOR Byron Carpenter (Landowner)
ADDRESS 840 H Road
CITY, STATE, ZIP Stockton, Ka. 67669
PHONE# (785) 425-6678 OPERATORS LICENSE NO. NA

SPOT LOCATION NE - NW - SE -
SEC. 5 TWP. 7 S. RGE 19 (E) or (W)
COUNTY Rooks
Date Well Completed 1-29-84
Date Plugging Commenced 11-4-99
Date Plugging Completed 11-4-99

Character of Well (Oil) Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 10-22-99 (date)
by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? was attached to CP-1

Producing Formation(s) 3250-3347 KC DA 3417-3419 + Depth to Top _____ Bottom _____ T.D. 3490
3444-3458 Arb.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.


Pressured up 8 5/8 S.P. 1000# 4 1/2 - Sq 25 sx Cmt w/100# hulls
F/w 10 sx gel, F/w 100 sx Cmt w/200# hulls mixed in cmt
Max P.S.I. 800# Shut-in P.S.I. 500#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Charley Farr Consl. Eng.
License No. 4580
Address 209W 33rd Hays, Ks
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Byron Carpenter
STATE OF Ks. COUNTY OF Rooks, ss.

Byron Carpenter (Employee of Operator or (Operator) of above-described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Byron Carpenter
(Address) 840 H Road Stockton Ka 67669



SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 99

Christy Phlieger
Notary Public

My Commission Expires: 9-17-2001

RECEIVED
KANSAS CORP COM
11-8-99
Form CP-4
Revised 12-92

Confirming Completion

3-2-14

STATE	KANSAS	CO.	ROOKS	MAP NO.		S-T-R	5-7S-19W	
OPER.	M & F LEASING					LOC.	NE NW SE	
	BOX 40 STOCKTON KS 67669						2310 FSL, 1650 FEL, S	
WELL	1 CARPENTER					ELEV.	1987 KB	
CONTR.	PIONEER DRLG					SUB STRUCTURE		
FIELD	LOCUST GROVE (MULTIPAY)							
IP	P 15.2 BOPD + 22.8 BWPD (LAN) 3250-3347, OA & (MARM) 3417-3419 & (ARB) 3444-3458							
API	15-163-22182	FR	10-6-83	COMP.	1-29-84		COMMINGLED	


SPUD 10-31-83, 8 5/8 @ 260 w/125 sx
 No DSTs
 RTD 3490 (11-6-83), log, 4½ @ 3486 w/150
 Perf (ARB) 3444-3458, 2500 GA (15%), swbd 1.25
 BOPH, RBP @ 3440, Perf (MARM) 3417-3419, 1300 GA
 (15%), swbd 3/4 BOPH + tr wtr, RBP @ 3400, Perf
 (LAN) 3345-3347, 500 GA (15%), RBP @ 3300, Perf
 (LAN) 3250-3251, 3233-3234, 3000 GA (15%), swbd 2½
 BFPH (40% oil), pulled plugs

IPP 15.2 BOPD + 22.8 BWPD (LANSING) 3250-3347, OA &
 (MARMATON) 3417-3419 & (ARBUCKLE) 3444-3458, COMMINGLED
 COMPLETED 1-29-84
 MARMATON - LOCUST GROVE - NEW PAY
 COMP ISSUED 3-13-84

KB LOG TOPS:

STONE CORRAL	1622 + 365
TOPEKA	2948 - 961
HEEBNER	3149 - 1162
TORONTO	3175 - 1188
LANSING	3191 - 1204
B/KANSAS CITY	3406 - 1419
MARMATON	3416 - 1429
ARBUCKLE	3440 - 1453
LTD	3490 - 1503
RTD	3490 - 1503
TD IN ARBUCKLE	

Corr: Field was Slate S (ARB)


Petroleum Information Corporation
A Subsidiary of A. C. Nelson Company
 © Copyright 1984 Reproduction Prohibited

RECEIVED
 KANSAS CORP OPM
 1989 NOV - 8 P 1:11