

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

15-163-21147-00-00

Give All Information Completely
Make Required Affidavit

COUNTY _____ Rooks _____ SEC. 5 TWP. 7-S RGE. 19 ~~N~~/W
Location as in quarters or footage from lines:
NE/SW/NE _____

NW			NE
SW			SE

Locate Well
correctly on above
Section Platt.

Lease Owner Cherokee Petroleum Corp.
Lease Name Griebel Well No. 1
Office Address 410 17th, Suite 2300, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed July 11, 1981
Application for plugging filed June 30, 1982
Plugging commenced July 26, 1982
Plugging completed August 8, 1982
Reason for abandonment of well or producing formation The well
ceased to produce hydrocarbons in paying quantities.
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation Arbuckle/LKC Depth to top 3118' bottom 3483' T.D. 3565'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	217'	
Arbuckle/LKC	Oil/H2O	3118'	3484'	5 1/2"	3626'	1088.88'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Dumped 5 scks cement with baler, top sand 3050'.
4 scks hulls, 15 gell, 70 cement, 7 scks gel, 8 5/8" plug, 70 scks cement all cement
50/50 pos 4% gel, 3% cc.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun-Cementing, Oil Field Service & Supply, Inc. 8-18-82

STATE OF Kansas COUNTY OF Decatur, ss.
James R. Betts Operator (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James R. Betts
James R. Betts, President
(Address)
P.O. Drawer 298, Oberlin, KS 67749

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 82

Rhonda Salem Notary Public.

My Commission expires: December 4, 1985

