

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20848 -00-00

LEASE NAME FARR

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from ~~N~~/N Line of Section (circle one)

330 Ft. from ~~W~~/W Line of Section (circle one)

LEASE OPERATOR ROY FARR HEIRS

SPOT LOCATION - NW - NW - NW

ADDRESS 209 W. 33 St.

SEC. 13 TWP. 7 S. RGE 19 (N) or (W)

CITY, STATE, ZIP HAYS, KANSAS 67601

COUNTY ROOKS

PHONE#(785 628-2513 OPERATORS LICENSE NO. 4580

Date Well Completed 11/1978

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 5/30/2000

Date Plugging Completed 5/30/2000

The plugging proposal was approved on 5/25/2000 (date)

by RICHARD WILLIAMS 5/25/2000 (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation(s) TORONTO & L.K.C. Depth to Top 3120 Bottom 3332 T.D. 3367

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
L.K.C.	SHALE & LIMESTONE	3120	3355	8 5/8	205'	0
Topela	Shale & Limestone	2894	3120	5 1/2	3385'	0
Anhydrite	Lime	1450	1484			
Dakota	Sand stone	500	1160'			

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3367 feet to Surf. feet each set.

Run tubing, spot 100 Sx. W/200# Hulls At 2450'

Perforate 2 holes @ 1448 and 2 holes @ 843, Spot 110 Sx. W/200# Hulls @ 1500' circulated cement to surface, pull tubing and squeeze 6 Sx. down casing to 500# shut in 400#.

Hook up to annulus and squeeze in 50 Sx. to 400# shut in 300#(All 60/40 Poz. 10% Gel.)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ron Geist and Allied Cementing Co.

License No. NA

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charles D. Farr

STATE OF Kansas COUNTY OF Rooks, ss.

Charles D. Farr (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles D. Farr

(Address) 209, W. 33 St, Hays, Ks, 67601

SUBSCRIBED AND SWORN TO before me this 31st day of MAY, 19 2000

Patty Dreiling
Notary Public

My Commission Expires: 8-30-02



RECEIVED
STATE CORPORATION COMMISSION

JUN 1 2000
6-1-2000
CONSERVATION DIVISION
Wichita, Kansas

R
Form CP-4
Revised 12-92

13-7-19 W

15-163-20848-0000

ALLIED CEMENTING CO., INC.

Farr #1
2894

Federal Tax ID [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>5-30-00</u>	SEC. <u>13</u>	TWP. <u>7S</u>	RANGE <u>19 W</u>	CALLED OUT	ON LOCATION <u>9:00 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>5:15 PM</u>
<u>FARR LEASE</u>	WELL # <u>1</u>	LOCATION <u>STOCKTON 7W-1N-1E-1/2 W</u>			COUNTY <u>ROOKS</u>	STATE <u>KS</u>	

CONTRACTOR GEIST WELL SERVICE

TYPE OF JOB OLD HOLE

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE 2 3/8" DEPTH 2400'

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER SAME

CEMENT AMOUNT ORDERED 3005 SKS 60/40 PPSZ 10% GEL

USED 2665 SKS 60/40 PPSZ 10% GEL 400' HULLS

COMMON _____ @ _____

POZMIX _____ @ _____

GEL _____ @ _____

CHLORIDE _____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

HANDLING _____ @ _____

MILEAGE _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

300 HELPER WAYNE

BULK TRUCK

280 DRIVER ANDREW

BULK TRUCK

_____ DRIVER _____

TOTAL _____

REMARKS:

MIX 1005 SKS CEMENT WITH 200' HULLS AT 2400' & DISPLACE.

MIX 110 SKS CEMENT WITH 200' HULLS AT 1400' & CIRCULATE TO SURFACE.

HOOK ON TO 5 1/2" CASING MIX 6 SKS CEMENT PRESSURE TO 500PSI. SHUT IN 400PSI.

MIX 50 SKS CEMENT DOWN BACKSIDE. PRESSURED TO 400PSI. SHUT IN 300PSI. THANK YOU

SERVICE

DEPTH OF JOB 2400'

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE _____ @ _____

MILEAGE _____ @ _____

PLUG _____ @ _____

_____ @ _____

TOTAL _____

CHARGE TO: ROY FARR HEIRS

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Charles Farr

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____