

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-23,189
00-00

LEASE NAME Graham

WELL NUMBER 2

330 Ft. from S Section Line

3,300 Ft. from E Section Line

SEC. 10 TWP. 7 RGE. 19 COR(W)

COUNTY Rooks

Date Well Completed 12-18-91

Plugging Commenced 12-18-91

Plugging Completed 12-18-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-91 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,478'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	218'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Fill hole w/heavy mud. Push bridge plug to 1,490', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 870', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 265', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Trust

(Address) Shields Bldg., Russell, KS.

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 92

Ruth Phillips
 Notary Public

Commission Expires: _____



RECEIVED
 STATE CORPORATION COMMISSION
 JAN 15 1992
 1-13-92
 CONSERVATION DIVISION
 WICHITA, KS