

KANSAS

J

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20121-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas
a3-68

Operator's Full Name J. Mark Richardson

Complete Address: 502 Union Center Wichita, Kansas

Lease Name Carstens Well No. 3410 I

Location NE SE NE Sec. 32 Twp. 7 Rge. 17 (E) (W) X

County Rooks Total Depth 3410

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7:45 P Day 28 Month 8 Year 1968

The Above well was plugged as follows:

RTD 3410' 8 5/8 csg set at 206' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massup
Well Plugging Supervisor

INVOICED

DATE 9/3/68
INV. NO. 8396-4