

DISTRICT CONSERVATION AGENT'S REPORT

*Handwritten initials*

15-163-00388-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE SW

SEC. 32 TWP. 7 RGE. 17

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Carsten

Operator Jones Shelburne Farmer Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3350 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 150' circulated with cement - 8 5/8" at 1005' with  
275 sax pumped in behind, followed by 75 sax pumped in between  
10" and 8 5/8", then squeezed with 100 sax cement through  
hole at 257'.

Circulated hole with heavy rotary mud, pushed wood plug to  
250', set 20 sax cement through drill pipe, pushed wood plug  
to 40', followed by 1/2 sack hulls and 10 sax cement to  
bottom cellar.

OCT 16 1950  
CONSERVATION DIVISION  
WICHITA, KANSAS

**PLUGGING**  
FILE SEC. 32 T. 7 R. 17  
PAGE 35 LINE 33

*Edmond Lee*  
District Conservation Agent  
Date 10-15-50