

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 463-21,070 ⁶⁰⁻⁰⁰ (of this well)

Operator's Full Name C.-P.-I, INC.

Complete Address PARKSIDE PLAZA, COLUMBIA, MISSOURI 65201

Lease Name SCHRYBEN Well No. #1

Location NW-SE-SE Sec 30 Twp. 7 Rge. 17 (E) (W) W

County ROOKS Total Depth 3345 ^{EE}

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor LAWBANCO DRILLING

Address NATOMA, KANSAS. License No. _____

Operation Completed: Hour 4:30 PM Day 12th Month MAY Year 1980

The above well was plugged as follows:

8 5/8" 160^{EE} SP. CMC w/ 110^{SE} COMMON QUICK SET

ORDERED 105^{SE} 50/50 POZMIX 6% GEL - 7 8 5/8" Plug. (Elev 1839)

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG. @ 780 EE w/ 70^{SE} CMT.

2ND PLUG @ 210 EE w/ 30^{SE} CMT.

3RD PLUG. → SOLID BRIDGE → HULL'S PLUG. → @ 40 EE to 0 w/ 10^{SE} CMT.

5^{SE} IN ENT HOLE

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED MAY 16 1980 5-16-80

Signed: [Signature]
Well Plugging Supervisor

DATE 5-17-80 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 2181w