

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20128-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Home - Stake Production, Company

Complete Address: Tulsa, Oklahoma

Lease Name Stambach Well No. 2

Location NW SE NW Sec. 33 Twp. 7 Rge. 17 (E) (W) X

County Rooks Total Depth 3412

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling, Inc.

Address: Victoria, Kansas License No.

Operation Completed: Hour 6:45P Day 5 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3412' 8 5/8 csg set at 248' cwc. Gmt. Mat. 100 sc 50-50 poz cmt. W/6% total gel
Gunned pits, circulated hreavy mud, set cementing plug at 660' and displaced 70 sc cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

OCT 9 - 1968

CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 10/9/68

INV. NO. 8595-W

10-9-68