

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-2010300-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1968
CONSERVATION DIVISION
Wichita, Kansas

4-22-68

Operator's Full Name Home Stake Production Co.,

Complete Address: Philtower Bldg., Tulsa, Oklahoma

Lease Name Stambach Well No. 1

Location NE NW SW Sec. 33 Twp. 7 Rge. 17 (E) (W) X

County Rooks Total Depth 3115

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons

Address: Victoria, Kansas License No.

Operation Completed: Hour 2:30 P Day 20 Month 4 Year 1968

The Above well was plugged as follows:

RTD 3115' Of 9" hole. 10 3/4" csg set at 225' cwc. 160 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 80 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 30 sc cement thru
drill pipe. Heavy mud to 30' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

Cementing Material 120 sc 50-50 poz cement W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/22/68

INV. NO. 7627-W