

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20034-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1967
7-24-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Chief Drilling Co. Inc.,

Complete Address: Box 797 Great Bend, Kansas

Lease Name Stambach Well No. 1

Location SE SW SW Sec. 33 Twp. 7 Rge. 17 (E) (W) X

County Rooks Total Depth 3440

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 9:30 A Day 21 Month 7 Year 1967

The Above well was plugged as follows:
RTD 3440' 8 5/8 csg set at 205' cwc 150 sc.
Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Mearns
Well Plugging Supervisor

DATE 7/24/67
INV. NO. 6012-W